DAFTAR PAKET PLTS FREENERGI



www.freenergi.com

WA: 082227927747

PAKET PLTS GRID TIE **EKONOMIS** FREENERGI

PAKET PLTS GRID TIE **EKONOMIS** 1 KWP

Nama Peralatan	Qty	Subtotal
Panel Surya 250 wp (Seri)	4	10.000.000
Dudukan Panel Surya	4	400.000
MC4	1	20.000
Kabel DC nyaf Supreme 1,5mm		100.000
MCB DC	1	75.000
Casing / Panel Box		450.000
Suoer Grid Tie (1 Phase)	1	3.500.000
Kabel AC Supreme NYM		100.000
MCB AC Schneider	1	20.000
Transport Charge untuk Alat		50.000
		14.715.000
Biaya perakitan alat		2.000.000
Biaya Total Alat		16.715.000
Jasa Instalasi		2.500.000
Biaya perizinan		2.000.000
Grand Total		21.215.000

PAKET PLTS GRID TIE **EKONOMIS** 2 KWP

Nama Peralatan	Qty	Subtotal
Panel Surya 250wp (Seri)	8	17.600.000
Dudukan Panel Surya	8	800.000
MC4	1	20.000
Kabel DC nyaf Supreme		100.000
MCB DC	1	75.000
Casing / Panel Box		450.000
Kenika Grid Tie Inverter (1 phase)	1	8.000.000
Kabel AC Supreme NYM		100.000
MCB AC		20.000
Transport Charge untuk Alat		50.000
		27.215.000
Biaya perakitan alat		4.000.000
Biaya Total Alat		31.215.000
Jasa Instalasi		4.500.000
Biaya perizinan		2.000.000
Grand Total		37.715.000

PAKET PLTS GRID TIE **EKONOMIS** 3 KWP

Nama Peralatan	Qty	Subtotal
Panel Surya 300 WP (Seri)	10	25.000.000
Dudukan Panel Surya	10	1.000.000
MC4	1	20.000
Kabel DC nyaf Supreme		100.000
MCB DC	1	75.000
Casing / Panel Box		450.000
SOLIS Grid Tie (1 Phase)	1	8.000.000
Kabel AC nym supreme 1,5mm		100.000
MCB AC	1	20.000
Transport Charge untuk Alat		50.000
		34.815.000
Biaya perakitan alat		6.000.000
Biaya Total Alat		40.815.000
Jasa Instalasi		5.500.000
Biaya perizinan		2.000.000
Grand Total		48.315.000

PAKET PLTS OFF GRID EKONOMIS FREENERGI

PAKET PLTS OFF GRID **EKONOMIS** 1 KWP (Sistem: 24 volt)

Nama Peralatan	Qty	Subtotal
Panel Surya 250wp (paralel)	4	10.000.000
Dudukan Panel Surya	4	400.000
MC4 4 cabang	1	20.000
Kabel DC nyaf Supreme 10mm		100.000
SCC 40a	1	100.000
Dioda Bridge 40a	1	55.000
Aki Basah 200 ah (seri)	2	5.400.000
Casing / Panel Box		450.000
MCB DC 50a	1	100.000
Kenika psw 1000 watt 24 volt	1	2.000.000
Kabel Supreme NYM 2.5mm		100.000
MCB AC 4 a	1	10.000
Transport Charge untuk Alat		50.000
		18.785.000
Biaya perakitan alat		2.500.000
Biaya Total Alat		21.285.000
Jasa Instalasi		2.500.000
Grand Total		23.785.000

PAKET PLTS OFF GRID **EKONOMIS** 2 KWP (Sistem : 24 volt)

Nama Peralatan	Qty	Subtotal
Panel Surya 250 wp (paralel)	8	17.600.000
Dudukan Panel Surya	8	800.000
MC4 4 cabang	2	135.000
Mc4 2 cabang	2	75.000
Kabel DC nyaf Supreme 25mm		100.000
SCC 80a	1	300.000
Dioda Bridge 80a	1	110.000
Aki Basah 200ah	4	10.800.000
Kabel DC nyaf Supreme 35mm		150.000
Casing / Panel Box		450.000
MCB DC 100a		200.000
Kenika psw 2000 watt 24 volt	1	3.000.000
Kabel AC nym		100.000
MCB AC 10a		20.000
Transport Charge untuk Alat		50.000
		33.890.000
Biaya perakitan alat		4.000.000
Biaya Total Alat		37.890.000
Jasa Instalasi		4.500.000
Grand Total		42.390.000

PAKET PLTS OFF GRID PRO FREENERGI

PAKET PLTS OFF GRID PRO 1 KWP (Sistem: 24 volt)

Nama Peralatan	Qty	Subtotal
Panel Surya 250wp (paralel)	4	10.000.000
Dudukan Panel Surya	4	400.000
MC4 4 cabang	1	20.000
Kabel DC nyaf Supreme		100.000
MPPT Epever	1	2.000.000
Dioda Bridge	1	55.000
Aki VRLA 200 ah (seri)	2	7.200.000
Casing / Panel Box		450.000
MCB DC Schneider	1	560.000
Inverter Pure Sine Wave Suoer 24 volt (1 phase)	1	3.000.000
Kabel Supreme NYM		100.000
MCB AC Schneider	1	220.000
Transport Charge untuk Alat		50.000
		24.155.000
Biaya perakitan alat		2.500.000
Biaya Total Alat		26.655.000
Jasa Instalasi		2.500.000
Grand Total		29.155.000

PAKET PLTS OFF GRID PRO 2 KWP (Sistem: 24 volt)

Nama Peralatan	Qty	Subtotal
Panel Surya 250 wp (paralel)	8	17.600.000
Dudukan Panel Surya	8	800.000
MC4 4 cabang	2	135.000
Mc4 2 cabang	2	75.000
Kabel DC nyaf Supreme		100.000
MPPT Suoer	1	5.850.000
Dioda Bridge	1	110.000
Aki VRLA 200ah (2 paralel diseri)	4	14.400.000
Kabel DC nyaf Supreme		150.000
Casing / Panel Box		450.000
MCB DC		300.000
Suoer Pure Sine Wave 24 volt (1 phase)	1	5.000.000
Kabel AC nym		100.000
MCB AC Schneider		400.000
Transport Charge untuk Alat		50.000
		45.520.000
Biaya perakitan alat		4.000.000
Biaya Total Alat		49.520.000
Jasa Instalasi		4.500.000
Grand Total		54.020.000

PAKET PLTS OFF GRID PRO 3 KWP (Sistem: 48 volt)

Nama Peralatan	Qty	Subtotal
Panel Surya 300 wp (paralel)	10	25.000.000
Dudukan Panel Surya	10	1.000.000
MC4 5 cabang	2	500.000
MC4 2 cabang	1	75.000
Kabel DC nyaf Supreme		100.000
Kabel DC nyaf Supreme (diameter lain)		150.000
MPPT Suoer	1	6.350.000
Dioda penyearah	1	55.000
Aki VRLA 200ah	8	28.800.000
Kabel DC nyaf Supreme (diameter lain)		100.000
Casing / Panel Box	1	450.000
MCB DC Schneider	1	650.000
Suoer Off Grid 48v (1 phase)	1	7.600.000
Kabel Supreme NYM		100.000
MCB AC Schneider	1	250.000
		71.180.000
Biaya perakitan alat		6.000.000
Biaya Total Alat		77.180.000
Jasa Instalasi		5.500.000
Grand Total		82.680.000

PAKET PLTS GRID TIE PRO FREENERGI

PAKET PLTS GRID TIE PRO 1 KWP

Nama Peralatan	Qty	Subtotal
Panel Surya 250 wp (Seri)	4	10.000.000
Dudukan Panel Surya	4	400.000
MC4	1	20.000
Kabel DC nyaf Supreme		100.000
MCB DC	1	360.000
Casing / Panel Box		450.000
Growatt (1 Phase)	1	7.100.000
Kabel AC Supreme NYM		100.000
MCB AC Schneider	1	250.000
Transport Charge untuk Alat		50.000
		18.830.000
Biaya perakitan alat		2.500.000
Biaya Total Alat		21.330.000
Jasa Instalasi		2.500.000
Biaya perizinan		2.000.000
Grand Total		25.830.000

PAKET PLTS GRID TIE PRO 2 KWP

Nama Peralatan	Qty	Subtotal
Panel Surya 250wp (Seri)	8	17.600.000
Dudukan Panel Surya	8	800.000
MC4	1	20.000
Kabel DC nyaf Supreme		100.000
MCB DC	1	36.000
Casing / Panel Box		450.000
Goodwe (1 Phase)	1	8.500.000
Kabel AC Supreme NYM		100.000
MCB AC Schneider		400.000
Transport Charge untuk Alat		50.000
		28.056.000
Biaya perakitan alat		4.000.000
Biaya Total Alat		32.056.000
Jasa Instalasi		4.500.000
Biaya perizinan		2.000.000
Grand Total		38.556.000

PAKET PLTS GRID TIE PRO 3 KWP

Nama Peralatan	Qty	Subtotal
Panel Surya 300 WP (Seri)	10	25.000.000
Dudukan Panel Surya	10	1.000.000
MC4	1	20.000
Kabel DC nyaf Supreme		100.000
MCB DC	1	360.000
Casing / Panel Box		450.000
Goodwe (1 Phase)	1	10.000.000
Kabel AC nym supreme		100.000
MCB AC Schneider	1	250.000
Transport Charge untuk Alat		50.000
		37.330.000
Biaya perakitan alat		6.000.000
Biaya Total Alat		43.330.000
Jasa Instalasi		5.500.000
Biaya perizinan		2.000.000
Grand Total		50.830.000

PAKET PLTS GRID TIE PRO 4 KWP

Nama Peralatan	Qty	Subtotal
Panel Surya 400 WP (Seri)	10	31.000.000
Dudukan Panel Surya	10	1.000.000
MC4	1	20.000
Kabel DC nyaf Supreme		100.000
MCB DC	1	360.000
Casing / Panel Box		450.000
Goodwe (1 Phase)	1	15.000.000
Kabel AC nym Supreme		100.000
MCB AC Schneider		200.000
Transport Charge untuk Alat		50.000
		48.280.000
Biaya perakitan alat		8.500.000
Biaya Total Alat		56.780.000
Jasa Instalasi		6.000.000
Biaya perizinan		2.000.000
Grand Total		64.780.000

PAKET PLTS GRID TIE PRO 5 KWP

Nama Peralatan	Qty	Subtotal
Panel Surya 400 wp (Seri)	12	37.200.000
Dudukan Panel Surya	12	1.200.000
MC4	1	20.000
Kabel DC nyaf Supreme		100.000
MCB DC	1	36.000
Casing / Panel Box		450.000
Goodwe (1 Phase)	1	15.600.000
Kabel Supreme NYM		100.000
MCB AC Schneider	1	250.000
Transport Charge untuk Alat		50.000
		55.006.000
Biaya perakitan alat		10.000.000
Biaya Total Alat		65.006.000
Jasa Instalasi		6.500.000
Biaya perizinan		2.000.000
Grand Total		73.506.000

PAKET PLTS GRID TIE PRO 7 KWP

Nama Peralatan	Qty	Subtotal
Panel Surya 400 wp (Seri)	18	55.800.000
Dudukan Panel Surya	18	1.800.000
MC4	1	20.000
Kabel DC nyaf Supreme		100.000
MCB DC	1	36.000
Casing / Panel Box		450.000
Growatt (3 Phase)	1	24.000.000
Kabel Supreme NYM 4mm		100.000
MCB AC Schneider	1	250.000
Transport Charge untuk Alat		50.000
		82.606.000
Biaya perakitan alat		14.000.000
Biaya Total Alat		96.606.000
Jasa Instalasi		9.500.000
Biaya perizinan		2.000.000
Grand Total		108.106.000

PAKET PLTS GRID TIE PRO 10 KWP

Nama Peralatan	Qty	Subtotal
Panel Surya 400 wp (Seri)	25	77.500.000
Dudukan Panel Surya	25	2.500.000
MC4	1	20.000
Kabel DC nyaf Supreme		100.000
MCB DC	1	36.000
Casing / Panel Box		450.000
Goodwe (3 phase)	1	62.000.000
Kabel NYM		45.000
mcb ac	1	600.000
Transport Charge untuk Alat		50.000
		143.301.000
Biaya perakitan alat		20.000.000
Biaya Total Alat		163.301.000
Jasa Instalasi		13.000.000
Biaya perizinan		2.000.000
Grand Total		178.301.000



www.freenergi.com

WA: 082227927747